

**NEW DELHI MUNICIPAL COUNCIL  
OFFICE OF THE EXECUTIVE ENGINEER ELECTRIC  
3RD FLOOR, MOHAN SINGH PLACE,  
BABA KHARAG SINGH MARG, NEW DELHI -110001**

QCM/ No. 01 /AEE M/N-II/EE(M/N) (E)-2017-18

Date:- 21-4-17  
Due Dated:- 28-4-17

M/s.....  
.....  
.....  
.....

Dear Sir,

Please quote your lowest rate for the following supply in sealed cover duly super-scribed with quotation number and date. Your sealed quotation must reach this office by 1500 hrs. on the due date. Quotations received will be opened at 15.30 hrs, on the same date in the presence of intending contractor or their authorized representatives.

It shall be the responsibility of the tenderer to ensure that their quotation reaches in time. As such the quotation received after the due date and time will not be considered.

**Subject:- Repairing of HT Cable fault from ESS Connaught Place to ESS Hindustan Times**

S. N	Description	Qty	Unit	Rate in Fig.	Rate in words	Amount
	<b>PART-A</b>					
1	Grond Penetrating Radar Survey ( GPRS) charges upto 01 Km.	01 Job	No.			
	<b>PART-B</b>					
2	Laying of PILCA/ PVC/ XLPE insulate cables of following sizes direct in ground including excavation, sand cushioning, protective covering and refilling the trench as per specifications in Hard Soil.					
2 a	Above 70 sq. mm/ 3C to 400 sq. mm/3C - Grade 11 KV (H.T.)	40	Mtr.			
3	Road cut of any thickness (metalled/ concrete) for one HT cable					
3 a	Road berm/ stonefoothpath/ brick foorthpath / C.C. slab/ approach gate.	40	Mtr.			
4	Supplying & laying of 125 mm dia. (O.D.) HDPE pipes ISI Marked PN-4 Class of following sizes across Road / Service Road by Trench Less Technology in various Roads/ Service Roads/ Main Gate in NDMC area.	105	Mtr.			

*Bron*  
AEE(M/N-II)

*Chander Singh*  
JEE(M/N-II)

5	Drawing of PVC/PILCA/ XLPE Power Cables of Grade 11 KV of the following sizes in existing RCC/ HDPE pipe. Closed Duct, subway or Sub Station.				
5 a	Above 150 sq. mm/3C and upto 1000 sq.mm/3C	105	Mtr.		
6	H.S. Type St. Th. Joint Box 11 KV HT XLPE Cable 400 Sq. mm.	2	Nos.	To be done by NDMC Departmentally	
	Total ( Part -A + Part - B) in Rs.				

**Taxes as Applicable**

**Grand Total:-**

**Total Amount in Words:-**

**OTHER TERMS AND CONDITIONS:-**

- Rates:** The rates will be written in figures as well as in words.
- Validity:** The rate should hold good for three months from the date of opening of the quotation. The validity period quoted less than 3 months will not be taken into consideration.
- Completion period:** The work of GPRS will as specified in the Q.C.M. is to be completed within 07 days from the work award and trenchless work for laying of HT Cable will be completed within 10 days after getting permission from Road cut Division.
- Compensation/Liquidated damages in the event of any delay the penalty @1% per day subject to a maximum of 10% will be imposed on the amount of total work against this Q.C.M.
- Risk & Cost:** The firm will be legally bound to execute the order after its acceptance within the completion period as stipulated in the work order. In case the firm fails to execute the order either in full or in part within the stipulated period this department reverses the right to get the work done at the risk & cost of the firm without making any reference and thereafter make recoveries from the firm if deemed necessary.
- Payment:** Our standard terms of payment is within 15/30 days after the receipt of bill in duplicate duly stamped and pre-receipted subject to timely completion of work as per the specifications and to the entire satisfaction of the Engineer-in-charge.
- Terms and conditions:** if any imposed by the firm other than the ones specified by us shall not be acceptable to us. The department reserves the right to accept the rates other than the lowest or reject any tender without assigning any reason or not award the work to any of the contractor quoting against this QCM.
- Guarantee Period:** 05 years ( item no. 6) from the date of making of HT Cable joint.
- Security Deposite and Gurantee For Due Performance:** ~~The security deposit @10% of the tender amount (5%Performance Guarantee&5% security Amount) shall be deducted from the contractors bill. The performance guarantee shall be refunded to the contractor soon after the completion of the work and recording of the completion certificate. The security will be refunded after Twelve months on satisfactory completion of the work.~~
- Arbitration:-** In the event of any dispute or difference arising between the contractor and the NDMC, the same will be referred to the sole Arbitrator appointed by the Spl. Officer/head of NDMC or his nominee whose decision shall be final and binding on both the parties. The venue of arbitration shall be National Capital Territory of Delhi.
- Agreement:** ~~The contractor will be required to execute an agreement on Rs. 50/ non-judicial stamp paper to be procured by him in case the value of the work Order amount to Rs. 25000/- and above.~~
- The site can be inspected by the contractor before quoting the rates.
- Location of site in front of Fire Station outer circle Connaught Place.

**SPECIFICATIONS:-**

**Laying of HT cables of all sizes.**

- The Cable laying work shall conform generally to specification as per IS 1255 latest edition and also according to Indian Electricity Rules. The HT cable laying work shall be inspected by the Electrical Inspector, Govt. of NCT Delhi.
- For one cable, the trench shall be 1.10 mts. deep for the cables above 11KV grade. The trench shall not be less than 0.30 mtrs. Wide. If more than one cable length is to be

*Signature*  
AEE (NCT)

*Signature*  
AEE (NCT)