

**QUOTATION**

**NEW DELHI MUNICIPAL COUNCIL  
OFFICE OF THE EXECUTIVE ENGINEER ELECTRIC  
3<sup>RD</sup> FLOOR, MOHAN SINGH PLACE,  
BABA KHARAG SINGH MARG, NEW DELHI -110001**

QCM/ No .30/AEE M/N-II/EE(M/N) (E)-2016-17

Dated :- 22/03/2017

Due Dated:- 27 /03/2017

M/s.....

.....

.....

.....

Dear Sir,

Please quote your lowest rate for the following work in sealed cover duly super-scribed with quotation number and date. Your sealed quotation must reach this office by 1500 hrs. on the same date. Quotations received will be opened at 15.30 hrs, on the due date in the presence of intending contractor or their authorized representatives.

It shall be the responsibility of the tenderer to ensure that their quotation reaches in time. As such the quotation received after the due date and time will not be considered.

**Name of work: Replacing of old existing two tier LT Panel board with new three tier LT Panel board at ESS Scindia House.**

Sr no./ item no.	Description of Item/ work	Qty	Rate in figures	Rate in Words	Amount
1	Dismantling of Existing two tier LT Panel Board, Crompton make including existing cables, bus coupling. etc at ESS Scindia House.	10 jobs			
2	Cartage, loading & unloading of two tier LT Panel board from ESS Scindia House to ESS Raja Bazar.	10 jobs			
3	Cartage, Dragging ,loading & unloading of new LT Panel board from 2 <sup>nd</sup> basement inside Palika Parking upto ESS Scindia House , LT Panel Room.	10 Jobs			
4	Installation, Testing & Commissioning of new LT Panel board at ESS Scindia House, complete as required.	10 Jobs			
5	Modification of Existing bus duct at Incomer end of LT Main No. 3, suitable for 1500 KVA Transformer oil type complete in all respect as required at site.	01 Job			
6	Providing & fixing of Thimble made of Al for 1000 sq.mm/1C cable for LT Panel side of TR no. 1 & 2.	14 nos.			
7	Earthing with copper earth plate 600x600x3 mm thick ( to be provided departmentally) including accessories and providing masonry enclosure with cover plate having locking arrangement and provision of watering pipe etc. complete with charcoal and salt as required.	02 nos.			
8	Fixing of 32x5 mm copper strip thick ( to be provided departmentally)in 40 mm dia GI Pipe from earth electrode as required including copper strip.	20 mtr			
9	Fixing of 32x5 mm copper strip thick ( to be provided departmentally)on surface or recess for connection etc. as required including copper strip.	30 mtr			

**Grand Total:-**

**All Taxes inclusive**

**Total Amount in Words:-**