

**NEW DELHI MUNICIPAL COUNCIL  
OFFICE OF THE EXECUTIVE ENGINEER ELECTRIC  
3RD FLOOR, MOHAN SINGH PLACE,  
BABA KHARAG SINGH MARG, NEW DELHI -110001**

QCM/ No. 12 /AEE M/N-II/EE(M/N) (E)-2017-18

Dated :- 18/08/17

M/s.....

Due Dated:-24/08/17

Dear Sir,

Please quote your lowest rate for the following supply in sealed cover duly super-scribed with quotation number and date. Your sealed quotation must reach this office by 1500 hrs. on the due date. Quotations received will be opened at 15.30 hrs, on the same date in the presence of intending contractor or their authorized representatives.

It shall be the responsibility of the tenderer to ensure that their quotation reaches in time. As such the quotation received after the due date and time will not be considered.

**Subject:- Repairing of HT Cable fault from ESS Raja Bazar No.6 to ESS Raja Bazar No.8.**

S. No.	Description	Qty	Unit	Rate in Fig.	Rate in words	Amount
<b>PART-A</b>						
1	Grond Penetrating Redar Survey ( GPRS) charges upto 01 Km.	01 Job	Job			
<b>PART-B</b>						
2	Laying of PILCA/ PVC/ XLPE insulate cables of following sizes direct in ground including excavator, sand cushioning, protective covering and refilling the trench as per specifications in Hard Soil.					
2a	Above 70 sq. mm/ 3C to 400 sq. mm/3C - Grade 11 KV (H.T.)	295	Mtr.			
3	Handling/Laying of cables which are not necessarily laid in ground but part of it going up to pole, panel, pillar & part in the building in open trench, pillar, panel or otherwise Grade 11 KV( H.T.)					
3a	HT Cable above 70 sqmm/3 C to 400 sqmm/3 C	5	Mtr.			
4	Road cut of any thickness ( metallised/ concrete) for one HT cable					
4a	Road berm/ stonefoothpath/ brick foorthpath / C.C. slab/ approchh gate.	295	Mtr.			
5	Supplying & laying of 125 mm dia. (O.D.) HDPE pipes ISI Marked PN-4 Class of following sizes across Road / Service Road by Trench Less Technology in various Roads/ Service Roads/ Main Gate in NDMC area.	50	Mtr.			
6	Drawing of PVC/PILCA/ XLPE Power Cables of Grade 11 KV of the following sizes in existing RCC/ HDPE pipe. Closed Duct, subway or Sub Station.					
6a	Above 150 sq. mm/3C and upto 1000 sq.mm/3C	50	Mtr.			
7	H.S. Type End Termination 150 sq. mm/3 C for XLPE Cable. Make- 3M/ Denson/ Raychem.	1	Nos.	Provided by department		
<b>Total in Rs.</b>						

Rate should be quoted inclusive of all taxes.

**Grand Total:-**

**Total Amount in Words:-**